# London Borough of Lambeth

## **REPAIRS WORKS ORDER**

<u>TO:</u>

|                        | raye i             |
|------------------------|--------------------|
| Order Number:          | 1860798/1          |
| Alternative Reference: | 1860798/1          |
| Version Number:        | 7                  |
| Contractor Site:       | LL-MEA             |
| Estimated Total Cost:  | £7862.41           |
| Work Programme:        | Responsive Repairs |
|                        |                    |
|                        |                    |

|                           | Issue Date:         | 04-JUL-16                      |
|---------------------------|---------------------|--------------------------------|
|                           | Priority:           | Priority 5-Ninety Working Days |
| LL-Mears Ltd (North Area) | Target Date:        | 03-MAR-2017 15:22              |
|                           | Right to Repair:    | Ν                              |
|                           | Asbestos:           |                                |
|                           | Litigation Applies: | Ν                              |
|                           | Tenant Information: |                                |
|                           | Appointment Date:   |                                |
|                           | Appointment Status: |                                |
|                           | Access Details:     | TO BE ARRANGED BETWEEN         |
|                           | Appointment Advice: |                                |
|                           |                     |                                |

### ADDRESS / CONTACT DETAILS:

# Raised By: Property in Repairs Contract Area: Telephone Property: Contact: Work RR-DMC-following recipt of crm action ref: 172544 informed that there may be a possible leak affecting and possibly also also

**ISSUED BY:** 

Location: Roof and Exterior Structure Notes:

|  | JOB DETAILS  | Job      | Unit         | Curr<br>Qty | Job<br>Price |
|--|--|----------|--------------|-------------|--------------|
| Job Location<br>SOR Code<br>Job Comment<br>SOR | Roof and Exterior Structure<br>RFR041<br>following recipt of crm action ref: 172544 informed that there<br>may be a possible leak affecting<br>INSPECTION; PROVIDE TYPED REPORT ON DEFECTIVE ROOF:In | I        | ITEM         | 1           | 26.34        |
| Description                                    | roof, remove all debris, plant, moss etc as necessary from rood to facili<br>take a holistic look at roof and prove clear typed reports  | •        |              | •           |              |
|  |  | Job      | Unit         | Curr        | Job          |
|  | JOB DETAILS  | Job      | Unit         | Curr<br>Qty | Job<br>Price |
| Job Location<br>SOR Code<br>Job Comment        | JOB DETAILS<br>Roof and Exterior Structure<br>RFR031   | Job<br>2 | Unit<br>SQME |             |              |

Page 1 of 3

London Borough of Lambeth

**REPAIRS WORKS ORDER** 

|                        | Page 2             | of 3 |
|------------------------|--------------------|------|
| Order Number:          | 1860798/1          | 0.0  |
| Alternative Reference: | 1860798/1          |      |
| Version Number:        | 7                  |      |
| Contractor Site:       | LL-MEA             |      |
| Estimated Total Cost:  | £7862.41           |      |
| Work Programme:        | Responsive Repairs |      |
|                        |                    |      |

|   | Work Programme: Responsive Repairs   |        |        |                  |                     |  |  |
|---|--|--------|--------|------------------|---------------------|--|--|
|   | Work Programme.  | Job    | Unit   | Curr             | Job                 |  |  |
|   | JOB DETAILS  |        |        | Qty              | Price               |  |  |
| Job Location<br>SOR Code<br>Job Comment | Roof and Exterior Structure<br>RFR043  | 3      | SQME   | 50               | 553.5               |  |  |
| SOR<br>Description                      | INSULATION; LAY UPTO 300MM THICK QUILT:Insulation; Supply and lay upto 300mm thick insulation quilt to loft area including gain access and moving/replacing contents within loft area in order to undertake work   |        |        |                  |                     |  |  |
|   | JOB DETAILS  | Job    | Unit   | Curr<br>Qty      | Job<br>Price        |  |  |
| Job Location<br>SOR Code<br>Job Comment | Roof and Exterior Structure<br>240101  | 4      | ITEM   | 1                | 468.07              |  |  |
| SOR<br>Description                      | SCAFFOLDING: PROVIDE NE 5M HIGH NE 10M GIRTH -Scaffolding: Provide, erect, maintain for a period not exceeding six weeks and dismantle on completion tubular steel scaffolding not exceeding 5.00m high, and not exceeding 10.00m girth, including ladders, pulley ropes, wheel fixings etc. |        |        |                  |                     |  |  |
|   |  | Job    | Unit   | Curr             | Job                 |  |  |
| Job Location<br>SOR Code<br>Job Comment | JOB DETAILS<br>Roof and Exterior Structure<br>CR225001   | 5      | METR   | <b>Qty</b><br>25 | <b>Price</b><br>240 |  |  |
| SOR<br>Description                      | FILLET:RENEW CEMENT MORTAR FILLET Fillet:Hack off existing and renew cement mortar fillet (1:3) and remove surplus spoil.  |        |        |                  |                     |  |  |
|   | JOB DETAILS  | Job    | Unit   | Curr<br>Qty      | Job<br>Price        |  |  |
| Job Location<br>SOR Code<br>Job Comment | Roof and Exterior Structure<br>CR431503  | 6      | SQME   | 25               | 2203.5              |  |  |
| SOR<br>Description                      | FLOOR TILES:RENEW QUARRY TILES Floor Tiles:Hack off quarry tiles, clear away, supply and lay new ne 152x152x17mm quarry tiles, on and including cement and sand bed, grout in tiles, and all necessary cutting and remove waste and debris.  |        |        |                  |                     |  |  |
|   | JOB DETAILS  | Job    | Unit   | Curr<br>Qty      | Job<br>Price        |  |  |
| Job Location<br>SOR Code<br>Job Comment | Roof and Exterior Structure<br>VE0130  | 7      | SQME   | 25               | 686.5               |  |  |
| SOR<br>Description                      | FLOORING:RENEW IN 19MM PLYWOOD Flooring:Renew any flooring with 19mm WBP plywood including denial joists and remove waste and debris, punch in nails, level to existing and make good including additional noggins and support battens as required.  |        |        |                  |                     |  |  |
|   | ESTIMATE   | ED TOT | AL COS | Т                | £7862.41            |  |  |

# London Borough of Lambeth

of 3

**REPAIRS WORKS ORDER** 

History of asbestos - please refer to the asbestos register. History of asbestos in block - please refer to the asbestos register